

## iSWM Construction Control Standard Details

Addendum to: **iSWM Technical Manual – Construction Controls**The following are a selection of 10 iSWM construction control BMP schematics chosen to be provided in standard details.

- 1. Rock Check Dams
- 2. Temporary Erosion Control Blankets
- 3. Dewatering Controls
- 4. Filter Tube Curb Inlet Protection
- 5. Hog Wire Weir Curb Inlet Protection
- 6. Curb Rock Sock On-Grade Curb Inlet Protection
- 7. Filter Tube Area Inlet Protection
- 8. Sediment Basin with Overflow Riser
- 9. Silt Fence
- 10.Stabilized Construction Exit

Created: January 2018




FIGURE 2.1 STANDARD CONSTRUCTION DETAIL - ROCK CHECK DAMS (1 OF 2)

#### **ROCK CHECK DAM GENERAL NOTES:**

- 1. SEE NCTCOG STANDARD SPECIFICATIONS (2017), SECTION 202.9 CHECK DAM (ROCK).
- 2. STONE SHALL BE WELL GRADED WITH SIZE RANGE FROM 1 1/2 TO  $\,3\,$  1/2 INCHES IN DIAMETER DEPENDING ON EXPECTED FLOWS.
- 3. THE CHECK DAM SHALL BE INSPECTED AS SPECIFIED IN THE SWPPP AND SHALL BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.
- 4. WHEN SILT REACHES A DEPTH EQUAL TO ONE-THIRD OF THE HEIGHT OF THE CHECK DAM OR ONE FOOT, WHICHEVER IS LESS, THE SILT SHALL BE REMOVED AND DISPOSED OF PROPERLY.
- 5. WHEN THE SITE HAS ACHIEVED FINAL STABILIZATION OR ANOTHER EROSION OR SEDIMENT CONTROL DEVICE IS EMPLOYED, THE CHECK DAM AND ACCUMULATED SILT SHALL BE REMOVED AND DISPOSED OF IN AN APPROVED MANNER.

FIGURE 2.1 NOTES ON ROCK CHECK DAM (2 OF 2)

ISWM™ TECHNICAL MANUAL CONSTRUCTION CONTROLS **BURY THE UP-CHANNEL** 4 INCH MINIMUM SIDE OVERLAP END OF THE BLANKET IN A 6" X 6" INCH TRENCH OR PER **EROSION CONTROL BLANKET MANUFACTURER** LITERATURE \_3' MÍN.₄ FOR SLOPE PROTECTION, NOT CHANNELS - 3' MIN. -3' MIN. SHEET FLOW STAPLES (TYP.) 12 INCH ON CENTER AT END OF ECB AT EACH SLOPE CHANGE, AND THROUGHOUT ECB AT SPACING RECOMEMENDED BY MANUFACTURER 3 FOOT MINIMUM OVERLAP AT ENDS OF BLANKETS. ECB AT HIGHER ELEVATION SHALL OVERLAP ON TOP OF LOWER ECB, OR PER MANUFACTURER LITERATURE. ECB ISOMETRIC PLAN VIEW N.T.S. ECB OVERLAP EXAMPLE N.T.S.

FIGURE 2.7 STANDARD CONSTRUCTION DETAIL - TEMPORARY EROSION CONTROL BLANKETS (1 OF 2)

#### **EROSION CONTROL BLANKETS GENERAL NOTES:**

- 1. SEE NCTCOG STANDARD SPECIFICATIONS (2017) SECTION 202.15.
- 2. PRIOR TO THE INSTALLATION OF ANY EROSION CONTROL BLANKETS, ALL ROCKS, DIRT CLODS, STUMPS, ROOTS, TRASH AND ANY OTHER OBSTRUCTIONS THAT WOULD PREVENT THE BLANKET FROM LYING IN DIRECT CONTACT WITH THE SOIL SHALL BE REMOVED. ANCHOR TRENCHING SHALL BE LOCATED ALONG THE ENTIRE PERIMETER OF THE INSTALLATION AREA, EXCEPT FOR SMALL AREAS WITH LESS THAN 2% SI OPE
- 3. INSTALLATION AND ANCHORING SHALL CONFORM TO THE RECOMMENDATIONS SHOWN WITHIN THE MANUFACTURER'S PUBLISHED LITERATURE FOR THE APPROVED EROSION CONTROL BLANKET. PARTICULAR ATTENTION MUST BE PAID TO JOINTS AND OVERLAPPING MATERIAL.
- 4. IN ABSENCE OF MANUFACTURE'S LITERATURE, A MINIMUM 11-GUAGE WIRE STAPLES, 6-INCHES IN LENGTH AND 1-INCH WIDTH WILL BE USED.
- 5. AFTER APPROPRIATE INSTALLATION, THE BLANKETS SHOULD BE CHECKED FOR UNIFORM CONTACT WITH THE SOIL, SECURITY OF THE LAP JOINTS, AND FLUSHNESS OF THE STAPLES WITH THE GROUND.
- 6. INSPECTION SHALL BE AS SPECIFIED IN THE SWPPP.

FIGURE 2.7 NOTES ON TEMPORARY EROSION CONTROL BLANKETS (2 OF 2)

ISWM™ TECHNICAL MANUAL CONSTRUCTION CONTROLS FILTERED WATER FLOW COURSE AGGREGATE, **SEWN IN SPOUT** ESTABLISHED GRASS, SEDIMENT MULCH, STRAW, OR CONTAINMENT OTHER PREPARED **FILTER BAG UNDERLAYMENT TO PUMPED** WATER PROTECT FILTER BAG (PER MANUFACTURERS RECOMMENDATIONS) PUMP DISCHARGE HOSE SECURED TO SPOUT FILTERED WATER FLOW SEDIMENT FILTER BAG PLAN VIEW SHOW LOCATIONS OF FILTER BAGS ON THE DRAWINGS. SIPHON HOSE PLACED IN SEDIMENT CONTAINMENT FILTER BAG -PUMP DISCHARGE HOSE WATER TO BE PUMPED FLOW SEDIMENT FILTER BAG PROFILE **DEWATERING CONTROL GENERAL NOTES:** 1. THE BAG SHOULD BE A NON-WOVEN, NEEDLE-PUNCHED, GEOTEXTILE THAT MEETS ASTM CRITERIA-D4632, D4833, D-3786, D-4355, D-4491, AND D-4751.

FIGURE 3.4 STANDARD CONSTRUCTION DETAIL - DEWATERING CONTROLS

2. CAPACITY, INSTALLATION, MAINTENANCE , AND REMOVAL OF BAGS AND PUMPS SHOULD CONFORM TO PUBLISHED MANUFACTURER

LITERATURE.






FIGURE 3.6 STANDARD CONSTRUCTION DETAIL - FILTER TUBE CURB INLET PROTECTION



# HOG WIRE WEIR CURB INLET PROTECTION ISOMETRIC VIEW N.T.S.




### **HOG WIRE WEIR CURB INLET PROTECTION CROSS SECTION**

N.T.S.

NOTE: THIS CONTROL WILL DECREASE THE CAPACITY OF THE INLET. IT SHALL ONLY BE USED WHEN AN ENGINEER HAS DETERMINED THERE IS ADEQUATE STORAGE OR POSITIVE OVERFLOW.

REFERENCE: NCTCOG STANDARD SPECIFICATIONS (2017), SECTION 202.14

FIGURE 3.7 STANDARD CONSTRUCTION DETAIL - HOG WIRE WEIR CURB INLET PROTECTION (1 OF 2)



#### HOG WIRE WEIR CURB INLET PROTECTION PLAN VIEW

N.T.S

#### TABLE EC1

INLET OPENING	MINIMUM NUMBER OF ROCK BAGS	
	TOP	FRONT
5'	2	3
10'	3	3
15'	3	4
20'	4	4

#### NOTES:

- 1.A SECTION OF FILTER FABRIC SHALL BE REMOVED AS SHOWN ON THIS DETAIL TO PROVIDE A 2" MINIMUM CLEAR OPENING, FABRIC MUST BE SECURED TO WIRE BACKING WITH CLIPS OR HOG RINGS AT THIS LOCATION.
- 2.INSPECTION SHALL BE MADE BY THE CONTRACTOR AND SILT ACCUMULATION MUST BE REMOVED WHEN DEPTH REACHES 2". 3.INLET PROTECTIONS SHALL BE REMOVED AS SOON AS THE SOURCE OF SEDIMENT IS STABILIZED.

FIGURE 3.7 STANDARD CONSTRUCTION DETAIL - HOG WIRE WEIR CURB INLET PROTECTION (2 OF 2)

CONSTRUCTION CONTROLS ISWM™ TECHNICAL MANUAL




FIGURE 3.9 STANDARD CONSTRUCTION DETAIL -CURB ROCK SOCK ON-GRADE CURB INLET PROTECTION (1 OF 2)

# CURB ROCK SOCK ON-GRADE CURB INLET PROTECTION GENERAL NOTES: 1. THIS DETAIL IS INTENDED FOR USE WITH ON-GRADE INLETS (NOT A LOW POINT) TO TRAP SEDIMENT. $2.\,\mathrm{DO}$ NOT INSTALL ON INLETS WHERE THE ROCK SOCKS WOULD EXTEND INTO AN ACTIVE TRAVEL LANE. 3. ROCK SOCKS MAY BE USED ON PAVED OR UNPAVED SURFACES. 4. MAXIMUM ROCK SOCK DIAMETER 4" TO 6". 5. MINIMUM OF 2 CURB ROCK SOCKS.

FIGURE 3.9 STANDARD CONSTRUCTION DETAIL - CURB ROCK SOCK ON-GRADE CURB INLET PROTECTION (2 OF 2)

ISWM™ TECHNICAL MANUAL CONSTRUCTION CONTROLS **OVERLAP ENDS TIGHTLY** 24" MINIMUM SECURE END **COMPLETELY SURROUND** FILTER TUBE OF LOG TO DRAINAGE ACCESS TO \*DIAMETER = XX" AS STAKE AS AREA DRAIN INLETS WITH SPECIFIED ON PLAN **DIRECTED EROSION CONTROL LOG** METAL OR TEMP. EROSION WOOD STAKES CONTROL LOG (12 " MIN.) 6" MIN. FLOW FLOW: STAKE OR USE **SANDBAGS** ON DOWNHILL SIDE OF INDET  $\nabla$ LOG AS NEEDED TO HOI D 1 1/2 " -2" IN PLACE (TYPICAL) BEDDING TRENCH FILTER TUBE AREA INLET PROTECTION PLAN VIEW FILTER TUBE "Y" INLET PROTECTION CROSS SECTION 2" x 2" WOOD N.T.S. or #3 REBAR, 2' TO 4' LONG. **EROSION CONTROL LOG** (AS SHOWN OR THROUGH THE PLACE EXCAVATED TUBE) MATERIAL ON UPHILL **FILTER TUBE** SIDE OF EROSION \*DIAMETER = XX" AS CONTROL LOG. SPECIFIED ON PLAN METAL OR WOOD STAKES MINIMUM 7 **DROP** INLET 1/2 " -2' 12" DIAMETER BEDDING MINIMUM TRENCH  $\nabla$ NOTE: COMPACT EXCAVATED SOIL TO PREVENT UNDERCUTTING.

FIGURE 3.13 STANDARD CONSTRUCTION DETAIL - FILTER TUBE AREA INLET PROTECTION

NOTE: SEE NCTCOG STANDARD SPECIFICATIONS (2017), SECTION 202.18

N.T.S.

EMBEDMENT EXAMPLE FOR FILTER TUBE

FILTER TUBE DROP INLET PROTECTION CROSS SECTION

N.T.S.

ISWM™ TECHNICAL MANUAL CONSTRUCTION CONTROLS STABILIZATION - RIP RAP, **EMERGENCY SPILLWAY -**MATTINGS OR OTHER ACCEPTABLE MATERIAL EXCAVATED AREA FOR STORAGE AS NECESSARY, SHAPE MAY VARY. SIDE SLOPES SHOULD 3:1 OR FLATTER. ENERGY DISSIPATION BLOCKS (AS NEEDED) DEWATERING **RISER DESIGN** COMPUTATION REQUIRED **OUTFALL PIPE** \*SPECIFIC DESIGN INFORMATION ON THE EROSION **EARTH BERM** CONTROL PLANS IS REQUIRED FOR EACH INSTALLATION **PLAN VIEW** N.T.S. **EMBANKMENT** 6' MIN. HIGH FLOW OUTLET STABILIZED WITH TEMPORARY OR **PERMANENT VEGETATION** 1' MIN. ▼ DESIGN HIGH WATER **EMERGENCY** SPILLWAY 1' MAX. **ELEVATION** DESIGN CAPACITY 1' MAX. 1 2 COMPACTED CLAY BERM SLOPE TO DRAIN ANCHOR BLOCK **STABILIZED** OUTLET **CROSS SECTION A-A** N.T.S.

FIGURE 3.20 STANDARD CONSTRUCTION DETAIL - SEDIMENT BASIN WITH OVERFLOW RISER

REFERENCE: NCTCOG ISWM CRITERIA MANUAL FOR SITE DEVELOPMENT AND CONSTRUCTION, SECTION 3.9 SEDIMENT BASIN.




FIGURE 3.28 STANDARD CONSTRUCTION DETAIL - FOR SILT FENCE (1 OF 2)

#### SILT FENCE GENERAL NOTES:

- 1. DESIGN SHALL SHOW ON THE DRAWINGS THE LOCATIONS WHERE OVERFLOW STRUCTURES SHALL BE INSTALLED. OVERFLOW STRUCTURES ARE REQUIRED AT ALL LOW POINTS AND AT A SPACING OF APPROXIMATELY 300 FEET WHERE NO LOW POINT IS APPARENT.
- 2. DESIGNER SHALL SHOW ON THE DRAWINGS THE LOCATIONS WHERE SILT FENCE IS TO BE TURNED UPSLOPE AT THE ENDS. UPSLOPE LENGTHS SHALL BE A MINIMUM OF 10 FEET.
- 3. POST WHICH SUPPORT THE SILT FENCE SHALL BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF ONE FOOT.
- 4. THE TOE OF THE SILT FENCE SHALL BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWNSLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW.
- 5. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL.
- 6. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH SUPPORT POST OR TO WIRE BACKING, WHICH IN TURN IS ATTACHED TO THE FENCE POST. THERE SHALL BE A 3 FOOT OVERLAP, SECURELY FASTENED WHERE ENDS OF FABRIC MEET.
- 7. INSPECTION SHALL BE AS SPECIFIED IN THE SWPPP. REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED.
- 8. SILT FENCE SHALL BE REMOVED WHEN FINAL STABILIZATION IS ACHIEVED OR ANOTHER EROSION OR SEDIMENT CONTROL DEVICE IS EMPLOYED.
- 9. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF HALF THE HEIGHT OF THE FENCE. THE SILT SHALL BE DISPOSED OF AT AN APPROVED SITE AND IN SUCH A MANNER AS TO NOT CONTRIBUTE TO ADDITIONAL SILTATION.
- 10. SEE NCTCOG STANDARD SPECIFICATIONS (2017), SECTION 202.5

FIGURE 3.28 NOTES FOR SILT FENCE (2 OF 2)

ISWM™ TECHNICAL MANUAL CONSTRUCTION CONTROLS LENGTH AS SHOWN ON PLANS **GRADE TO PREVENT RUNOFF** FILTER FABRIC FROM LEAVING SITE 6" MIN. PAVED SURFACE **EXISTING GRADE PROFILE VIEW** N.T.S. **RADIUS** = 5' MIN. LENGTH (MIN. 50') GRADE TO DRAIN AWAY FROM STABILIZATION AND STREET PAVED SURFACE WIDTH (W) 20' MIN. FOR < 5 AC SITES 30' MIN. FOR > 5 AC SITES TRANSITION TO **PAVED SURFACE** R.O.W. DRAINAGE MUST FLOW AWAY FROM ENTRANCE

FIGURE 3.29 STANDARD CONSTRUCTION DETAIL - STABILIZED CONSTRUCTION EXIT (1 OF 2)

**PLAN VIEW** 

ENTRACE MUST BE SLOPED SO THAT STORM WATER IS NOT ALLOWED TO

N.T.S.

#### STABILIZED CONSTRUCTION ENTRANCE GENERAL NOTES:

- 1. SEE NCTCOG STANDARD SPECIFICATIONS (2017), SECTION 202.11
- 2. THE THICKNESS SHALL NOT BE LESS THAN 6 INCHES.
- 3. STONE SHALL BE 3 TO 5 INCH DIAMETER COURSE AGGREGATE, NO CRUSHED PORTLAND CEMENT CONCRETE ALLOWED.
- 4. LENGTH SHALL BE SHOWN ON PLANS, WITH A MINIMUM LENGTH OF 50 FEET.
- 5. THE WIDTH SHALL BE NO LESS THAN 20' FOR SITES LESS THAN 5 AC, AND 30' FOR SITES GREATER THAN 5 AC, AT ALL POINTS OF INGRESS OR EGRESS.
- 6. WHEN NECESSARY, VEHICLES SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO A PUBLIC ROADWAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE WITH DRAINAGE FLOWING AWAY FROM BOTH THE STREET AND THE STABILIZED ENTRANCE. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATERCOURSE USING APPROVED METHODS.
- 7. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PAVED SURFACES. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND. ALL SEDIMENT SPILLED, DROPPED, WASHED, OR TRACKED ONTO PAVED SURFACES MUST BE REMOVED IMMEDIATELY.
- 8. THE ENTRANCE MUST BE PROPERLY GRADED OR INCORPORATE A DRAINAGE SWALE TO PREVENT RUNOFF FROM LEAVING THE CONSTRUCTION SITE.
- 9. INSPECTION SHALL BE SPECIFIED IN THE SWPPP.

FIGURE 3.29 NOTES FOR STABILIZED CONSTRUCTION EXIT (2 OF 2)